#37. Opposite Sagar Service Station

BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/02/2020-21 Date: 10.06.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT42932

SCHEDULE -B

Name of Work: Pot hole filling in Jalahalli surrounding areas of Bhovi Colony Khata nagara Sidhartha nagara Jalahalli colony in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	367.35	KSRRB 300-1. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	299.00	Rupees Two Hundred Ninety Nine Only
2	275.51	Providing, laying , spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	2098.00	Rupees Two Thousand Ninety Eight Only
3	1836.76	Filling potholes and patch Repairs with Bituminous Concrete, 40mm. Removal of all failed material, trimming of completed excavation to provid firm vertical faces, clearing of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to from a smooth continuous surface, all as per clause 3004.2	Sqm	341.00	Rupees Three Hundred Forty One Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP